

# STIWA Zubau Trakt C

Attnang-Puchheim, Austria





# Project Description

STIWA Holding GmbH, based in Attnang Puchheim, is an experienced company in the field of product and high-performance automation and has around 2,200 employees. Furthermore, the product and software development for production automation, the supplier production of high-quality metal and plastic components, energy-efficient building technology and laboratory automation are among the core competencies of the Austrian company.

From 2019 to 2020, Lindner was commissioned to design the interior of an office building and an assembly hall. Over 5,000 m<sup>2</sup> of heated and chilled ceilings, 5,500 m<sup>2</sup> of floor space and 1,000 m<sup>2</sup> of dry lining were successfully installed here according to a strict schedule. The integrated Plafotherm<sup>®</sup> heated and chilled ceiling systems create a pleasant room climate, especially in conference rooms and offices, and fit perfectly into the overall picture thanks to the clean design and the homogeneous ceiling surface. The extremely light raised floor system LIGNA allows the lowest possible emission values and withstands fire for up to 30 minutes. The hollow floor system Floor and more<sup>®</sup> ensures pleasant acoustics and, with its dark surface, forms a visual contrast to the light room decor.

## General

<b>Building Type</b>	Office buildings
<b>Company Division</b>	Lindner GmbH
<b>Completion</b>	2019
<b>Client</b>	STIWA Holding GmbH

# Completed Works

- **Ceilings**
  - Heated and Chilled Post Cap Ceilings  
Plafotherm<sup>®</sup> B 100 3820 sqm
  - Heated and Chilled Hook-On Ceilings 230 sqm
- **Floors**
  - Chipboard panels  
LIGNA 3990 sqm
  - Calcium sulphate panels  
FLOOR and more<sup>®</sup> 190 sqm



